

Operating Performance Schedule

Yes **No**

Unit Proposal will have a direct communication link with Counterparty's Control Center that enables Counterparty to control the operation of the unit under automatic generator control (in control area) or a combination of dynamic/block scheduling (outside of control area)

x	
---	--

Counterparty will be able to operate the unit to provide voltage support for the system:
In control area

x	
---	--

Counterparty will be able to operate the unit to provide frequency control for the system:
In control area

x	
---	--

The proposed project will be Fully Dispatchable by Counterparty.

x	
---	--

The proposed project will be Fully Schedulable by Counterparty.
System Power Proposal

x	
---	--

The Bidder agrees to coordinate its maintenance schedule with Counterparty.

x	
---	--

The level of on-site fuel storage (approximate equivalent hours of operation at full load without refilling).

18 hrs

Operating Performance Schedule

(Continued)

Operating Performance Evaluation Criteria

The maximum capacity level at which the plant may be operated while on AGC	<u>540</u> MW
The minimum capacity level (MW) at which the plant may be operated	<u>310</u> MW
The minimum capacity level (MW) while on AGC	<u>310</u> MW
The guaranteed start time required to bring each unit from a cold start to minimum load would be:	<u>30</u> minutes
The guaranteed ramp rate for the plant from the minimum loading level:	<u>45</u> MW/min
The ramp rate for the plant from the minimum loading level while on AGC	<u>14</u> MW/min
The approximate maximum number of starts (per plant) that Counterparty would be allowed per year (Test starts and starts after a forced outage or unscheduled maintenance will not be included when determining the number of starts requested by Counterparty)	<u>160</u> starts/year
The minimum run time when the plant has been dispatched on line would be:	<u>8</u> hours
The minimum down time when the plant has been taken off-line would be:	<u>4</u> hours
The maximum number of hours during a year that Counterparty would be allowed to operate the plant (subject to the air permit limits):	<u>8760</u> hours